



NOTE:

1. BACKFILL MATERIAL AND COMPACTION SHALL BE IN CONFORMANCE WITH SILVER LAKE WATER AND SEWER DISTRICT STANDARDS AND/OR COUNTY, CITY, STATE PERMIT REQUIREMENTS.
2. PIPES SHALL BE RESTRAINED IN FILL OR PREVIOUSLY DISTURBED MATERIAL.
3. CLAY OR BENTONITE DAMS SHALL BE INSTALLED ACROSS THE TRENCH AND TO THE FULL DEPTH OF THE GRANULAR MATERIAL IN ALL AREAS OF STEEP SLOPES, STREAM CROSSINGS AND WETLAND TO PREVENT MIGRATION OF WATER ALONG THE PIPELINE.

**SANITARY SEWER TRENCH
SECTION (PVC/GRAVITY)**

**Silver Lake Water and Sewer District
STANDARD DETAILS**